



3D Dimensional Control in Shipbuilding & Plant Project

NewMethodology

01 About SAMIN

World's #1 in Dimensional Control

Shipbuilding



Offshore Plant



Buildings



Refinery, Chemical and other Plant



2006



2018



Software Solutions



- ▶ 3D Dimensional Control Software
- ▶ Laser Scan Data based Analysis Software
- ▶ Laser Scan Data based Simulation Software
- ▶ Smart Pen Solution
- ▶ Production Management Solution

3D Survey & Analysis Services




- ▶ Client's 3rd Party Dimensional Inspection
- ▶ Verification of 3D As-built Dimension
- ▶ Total Station based Dimensional Survey at Fabrication & Installation Phase

Training & Consulting



- ▶ Dimensional Control Planning
- ▶ Dimensional Control Methodology
- ▶ D.C Execution & Reporting

3D Laser Scanning




- ▶ 3D Scanning for Plant, Building, Ship and Offshore
- ▶ Installation, Hook Simulation
- ▶ Scan Data Registration

Objective of Dimensional Control is to find and fix all errors to achieve First Time Setting

- Dimension Quality Management is all activities related to fabricated objects meeting pre-defined tolerances
- Dimension Control can be approached in two ways :
 - Active Approach: Measures taken to prevent module/block deformation during production
 - Adaptive Approach: Management of controlling deformations occurred during fabrication or installation
- **Always better to fix everything before leaving the shop**

Find and Fix errors during Fabrication



<3D Design>




<Production Block>



	Item	Tolerance
①	Length(3D)	±5mm
②	Width(Height)	±5mm
③	Level	±5mm
④	Verticality	±3mm
⑤	Difference on the edge	±2mm
⑥	Welding Reserve	Standard
⑦	Edge B/H	0~+2mm
⑧	LONG. Angle	±3mm

< Dimensional Control Standard >

Run 3D Installation Simulation to preempt problems during installation



Clash Free – One Time Setting

<Erection>

<Erection>



<Extra work for the error correction>




3D Dimensional Control



- Getting measurements in 2D using ruler, plumb or even total station doesn't provide enough information to understand deformation of structures.

2D Measurement

Plumb





Ruler/Tape line



Only checks lengths


Lengths might be correct but..



The module is actually deformed

Core of 3D Dimensional Control Methodology is Accuracy & Speed

- Plan – Quickly generate Check Plan using 3D Drawings
- Measure – Measurements using our own S/W can accurately measure large structures fast!
- Analyze – Check dimensions or run simulation in minutes




World's #1 Proprietary Software for analyzing large structures using point cloud data

- Design vs As-Built: Comparison of 3D Drawings with Actual Measurements
- As-Built vs As-Built: Comparison of Actual Measurements with another Actual Measurements


3D Laser Scanner



Design vs. As-Built




As-Built vs. As-Built




Total Station



Design vs. As-Built






As-Built vs. As-Built



SAMIN's proprietary 3D Scan data based analysis solution




More than 200% Faster



06 Analysis : Design vs As - Built


Laser Scan data based dimensional quality control using 3D Design and As-Built Data

- Check vessels, plant modules, and equipments against 3D Model
- Make all corrections before leaving the shop



Laser Scan data based installation simulation of As-Built vs As-Built Data

- Run Simulation of to be installed vessels, equipments and modules
- Make all necessary corrections before leaving the shop
- Achieve First Time Installation




3D Dimension Control of Fabricated Modules and Installation Simulation during production 3D Analysis for Operation, Maintenance, and Retrofit after production

Production Phase


Pre-Fabrication



Fabrication



Erection
/Installation



- 3D Dimension quality control in accordance with drawings
- Module/Equipment Installation Simulation to account for errors during installation
- Module/Equipment installation location verification

Operation Phase


Operation
& Maintenance




Revamp
& Retrofit




- Acquisition of As-Built Data
- Deformation verification of structures
- Installation simulation during retrofit



<Shipbuilding – Block Construction Method>



<Plant – Modular Construction Method>



<Building – Modular Construction Method>

More than 120 satisfied clients and partners globally

- **KOREA:** HHI,SHI,GS E&C, POSCO A&C, SAMSUNG ENG,GS Caltex etc.
- **EUROPE :** JAN DE NUL
- **SINGAPORE:** Sembcorp, Keppel Offshore&Marine, ST Engineering
- **CHINA:** ZPMC, BaoSteel, CSSC, DSIC Group, and 80 other companies
- **JAPAN:** Sumitomo Heavy Industry, and 15 other companies
- **USA:** Keppel AmFELS
- **INDIA:** CEMS (Center of Excellence in Maritime and Ship Building)
- **TAIWAN :** CSBC, Lung Teh Shipbuilding.